



VIKRAMA SIMHAPURI UNIVERSITY
NELLORE-524 320

CIVIL WORK NOTIFICATION

Last Date for submission of Application: 05.01.2021

Filling the ground with close graded granular sub-base material at open air theatre of Mahakavi Tikkana Kalakshetram (Dr. APJ Abdul Kalam Bhavn) in Vikrama Simhapuri University College:-

1. Earth work excavation

1 x 2 x 37.2m x 7.4m x 0.10m 55.06 cu.m

Deduct Room Portion

1 x 1 x 5.45m x 4.10m x 0.10m (-)2.23 cu.m

.....

52.83 cu.m x 179.40 / 1 cu.m = Rs. 9,478.00

.....

2. Collection and supply of close graded granular sub-base material

1 x 2 x 37.2m x 7.4m x 0.10 55.06 cu.m

Deduct Room Portion

1 x 1 x 5.45 x 4.10m x 0.10m (-) 2.23 cu.m

.....

52.83 cu.m x 820.70/ 1 cu.m = Rs. 43,358.00

.....

3. Conveyance of material from outside the

building to ground by head loads from

50 to 100 metres. 52.83 cu.m x 65.70/1 cu.m = Rs. 3,471.00

4. Spreading the material 52.83 cu,m x 28.74/1 cu.m = Rs. 1,518.00

5. Provision for unforeseen items if any L.S. = Rs. 2,175.00

.....
Rs. 60,000.00
.....

