



VIKRAMA SIMHAPURI UNIVERSITY
NELLORE-524 320

CIVIL WORK NOTIFICATION

Last Date for submission of Application: 21.11.2020

Filling the ground with stone dust at open air theatre of Mahakavi Tikkana Kalakshetram (Dr APJ Abdul Kalam Bhavan) in Vikrama Simhapuri University College, Nellore.

The following is the tentative estimate prepared for taking up of the above said work.

A) Earth work excavation

$$1 \times 2 \times 37.2 \text{m} \times 7.4 \text{m} \times 0.10 \text{m} = 55.06 \text{ cu.m}$$

Deduct Room Portion

$$1 \times 1 \times 5.45 \text{m} \times 4.10 \text{m} \times 0.10 \text{m} = (-) 2.23 \text{ cu.m}$$

$$52.83 \text{ cu.m} \times 179.40 / 1 \text{ cu.m} = \text{Rs. } 9,478.00$$

B) Collection and supply of
stone dust from approved quarry

$$1 \times 2 \times 37.2 \text{m} \times 7.4 \text{m} \times 0.10 \text{m} = 55.06 \text{ cu.m}$$

Deduct Room Portion

$$1 \times 1 \times 5.45 \text{m} \times 4.10 \text{m} \times 0.10 \text{m} = (-) 2.23 \text{ cu.m}$$

$$52.83 \text{ cu.m} \times 657.70 / 1 \text{ cu.m} = \text{Rs. } 34,746.00$$

$$\text{Spreading of stone dust} = 52.83 \text{ cu.m} \times 28.74 / 1 \text{ cu.m} = \text{Rs. } 1,518.00$$

C) Labour charges to lift the dust from outside
the building to Mahakavi Tikkana Kalakshetram

LS Rs. 3,000.00

D) Provision for unforeseen if any

Rs. 1,258.00

Rs. 50,000.00

Sd/-REGISTRAR